

FINISHED SURFACE TO BE GRADED PER THE ARCHITECT OR ENGINEERS SPECIFICATIONS AND READY FOR SEEDING, SODDING OR PLANTING. PLANT MATERIAL "TBD" AND CAN GROW THROUGH THE SOX WITHOUT COMPROMIZING THE SOX'S STABLE.

DEPTH OF BACKFILL COVER MATERIAL WILL VARY DEPENDING ON EXISTING AND FINISHED SLOPE. MATERIAL CAN BE THE SAME AS SOX BACKFILL MATERIAL.

1/4" DIAMOND BRAIDED POLY CORE ANCHORING ROPES.

NOTE: LOWER SOX ROPE CHANNEL MUST BE CONNECTED TO BOTH THE UPPER AND LOWER STAKE AS SHOWN BELOW.

18' DREDGESOX DRAPED OVER THE EXISTING BLOCK WALL AND BACKFILLED WITH SITE OR PROJECT SPECIFIC BACKFILL. BACKFILL MATERIAL SHOULD BE COARSE AND NO LESS THAN 120 MICRONS AND IS TYPICALLY ONE OF THE FOLLOWING MATERIALS (sand, topsoil, aeration plugs/cores, dredging spoils or and organic compost type mixture). IT IS RECOMMENDED THAT ALL FILL MATERIALS BE TESTED FOR PARTICLE SIZE AND FILTRATION PROPERTIES PRIOR TO INSTALL. NON-DREDGED BACKFILL CAN ALSO BE WASHED OR WATER SETTLED INTO THE SOX FOR STABILITY AND COMPACTION PURPOSES.

STEEPNESS OF SHORELINE GRASSED SLOPE TO BE SPECIFIED BY ARCHITECT OR LAKE ENGINEER.

STAKES SHALL BE PLACED 3' O.C. AROUND THE ENTIRE PERIMETER OF THE WATER FEATURE. TOP AND BOTTOM STAKES ARE TO BE OFFSET BY 18". TOP STAKES ARE TO BE INSTALLED INTO STABLE SUBSTRATE. BOTTOM STAKES ARE TO SET THE EDGELINE AND ARE GENERALLY JUST ABOVE THE ERODED EDGE INTO STABLE SUBSTRATE. STAKES AND ROPE TO BE RECESSED BELOW FINISHED GRADE. DEPTH & TYPE OF ANCHOR MAY VARY BASED ON SUBGRADE MATERIAL & ANCHORING METHOD.

EXISTING BLOCK WALL, REMOVE THE TOP TWO BLOCKS AND RE-GRADE AREA FOR INSTALL OF SOX. SOX TO BE DRAPED OVER BLOCK WALL. (TYPICAL SYMBOL)

REMOVED BLOCKS CAN BE GENTLY PLACE AT BOTTOM OF SOX PRIOR TO BACK-FILLING WITH MATERIAL

EXISTNG OR COMPACTED SUBGRADE (TYP SYM)

EXISTING SURFACE GRADE OR WATERWAY SURFACE SLOPE PER LOCAL CODE OR LAKE ENGINEER. (TYPICAL SYMBOL)

NOTE: THIS DRAWING IS A "DIAGRAMMATIC ILLUSTRATION" OF A SOX INSTALL METHOD.

DETAIL QUESTIONS - Call: (408)461-0324 or Email: dginkel@soxerosion.com

TYPICAL DREDGESOX INSTALL DETAIL

SHORELINE REPAIR TREATMENT OVER BLOCK WALL



CORPORATE OFFICE:

950 PENINSULA CORPORATE
CIRCLE, SUITE 3018
BOCA RATON, FL 33487

(561)501.0057
WWW.SOXEROSION.COM

DRAWN BY:
D. GINKEL

APPROVED BY:
RL & BF

SCALE: N.T.S.

PROJECT:

DETAIL:

DATE: 3/3/2020
REVISIONS: 7/13/2020